




Gym Flooring

Salvaged from Doyle High School in Livingston, LA, this gym floor's original Purple, Black and Brown paint lines have been reshuffled into a confetti of colorful stripes and marks. Like most gym floors, the material is a high grade of maple with a clear finish. The original tongue and groove remains intact.

CUT AND PASTE SPECIFICATION INTO APPROPRIATE CSI DIVISION

09 64 20 — Reclaimed Wood Flooring

06 42 00 — Wood Paneling

MANUFACTURER

Pioneer Millworks
1180 Commercial Dr
Farmington, NY 14425

MATERIALS

Product: Gym Flooring

Collection: Reclaimed

Species: Maple

Texture: Smooth Planed

Source: Athletic Facility Deconstruction

Color: Tones may range from cream to brown.

Unlimited color variation is inherent to the product.

Grade: Gym Flooring

Finish: Paint Color Varies

Hardness: 1300

(Janka Ball Test ASTM D1037-96A, Natural wood products have no minimum hardness since hardness is a characteristic of species and cannot be controlled)

DIMENSIONS & MILLING

Solid (Original Finish)

Thickness: 3/4" – 1"
varies per batch

Width: 3" nominal

Length: 12" – 10' random

Profile: **AS-FOUND**
Tongue and Groove

ADDITIONAL INFORMATION

Heartwood: No Restriction

Grain: No Restriction

Knots: No limitations on sound knots.

Surface defects from chipped or open knots may be present.

Voids: Nail, bolt and other mechanical holes can be present and occasionally reach 3/8" in diameter.

Surface defects from insect marks, including pin holes may be present. Peg or bolt holes are often left open in longer planks.

Discoloration: None

Checks: None

Moisture Content: Generally 6–12%

CERTIFICATIONS & LEED INFORMATION

FSC® Claim: FSC® Recycled 100% (SCS-COC-003998-D)

MRc3: Materials Reuse

(materials used for this credit cannot be applied to MRc4 or MRc5)

MRc4: Recycled Content, 100% Post-Consumer Recycled Content

(materials used for this credit cannot be applied to MRc3 or MRc7)

MRc5: Regional Materials (call for details)

INSTALLATION RECOMMENDATIONS

Overage: Minimum 10% additional material

For on-site grading, trimming and installation factors.

Climate: As with any wood flooring or paneling product, the room temperature should be held at a consistent range between **60-80° F** with relative humidity between **30-60%**.

Environmental conditions consistently outside of these parameters could result in product performance issues.