

# Foundry Oak

Salvaged from a historic furniture warehouse in High Point, North Carolina, this hardy oak floor was underfoot for a century of manufacturing. Material within this batch varies in color from golden brown to charcoal grey and may include occasional paint, old machine oil stains, and a range of wear marks. A great choice for commercial applications, this floor's unique appearance adds an instant and authentic industrial character to any environment.

## Source Location: High Point, NC

Dating back to the 1920's, this historic building was most recently occupied by the Haworth Seating Plant. Until its closure in 2021 the facility still had a working steam whistle and a boiler that heated the building with wood scraps. Following World War 2 it was estimated that 60% of all furniture that was made in America was manufactured within a 150 mile radius of High Point.

# CUT AND PASTE SPECIFICATION INTO APPROPRIATE CSI DIVISION

09 64 20 — Reclaimed Wood Flooring

06 42 00 — Wood Paneling

#### **MANUFACTURER**

Pioneer Millworks 1180 Commercial Dr Farmington, NY 14425

#### **MATERIALS**

Product: Foundry Oak
Collection: Reclaimed

Species: Domestic Red and White Oak

Texture: Original surface patina with a light wire-brushing

Source: Industrial Deconstruction

Color: Tones may range from golden brown to charcoal grey.

May include occasional paint, old machine oil stains, and a range of wear marks.

**Grade:** Foundry Oak **Finish:** Unfinished

Available prefinished upon request

Hardness: 1260

(Janka Ball Test ASTM D1037-96A, Natural wood products have no minimum hardness since hardness is a characteristic of species and cannot be controlled)

### **DIMENSIONS & MILLING**

Solid (Unfinished)

Thickness: 3/4''-1'' Profile: AS-FOUND Tongue and Groove

Width: 3" nominal

Length: 12"-10' random

## **ADDITIONAL INFORMATION**

Heartwood: No Restriction

Grain: No Restriction

Knots: No limitations on sound knots.

Surface defects from chipped or open knots may be present.

Voids: Nail, bolt and other mechanical holes can be present and occasionally reach 3/8" in diameter.

Surface defects from insect marks, including pin holes may be present. Peg or bolt holes are often left open in longer planks.

Discoloration: No Limitation

Checks: Structural checks not affecting the integrity of the plank, once installed, are allowed and more prevalent

as the width of the material increases.

Moisture Content: Kiln dried 6-9% prior to milling.

## **CERTIFICATIONS & LEED INFORMATION**

FSC® Claim: FSC® Recycled 100% (SCS-COC-003998-D)

MRc3: Materials Reuse

(materials used for this credit cannot be applied to MRc4 or MRc5)

MRc4: Recycled Content, 100% Post-Consumer Recycled Content (materials used for this credit cannot be applied to MRc3 or MRc7)

MRc5: Regional Materials (call for details)

### INSTALLATION RECOMMENDATIONS

Overage: Minimum 10% additional material

for on-site grading, trimming and installation factors.

Climate: As with any wood flooring or paneling product, the room temperature should be held at a consistent range between 60-80° F with relative humidity between 30-60%.

Environmental conditions consistently outside of these parameters could result in product performance issues.